



- All utilities shall be located and verified on site by the Contractor prior to construction.

 2. All supply and installation of labour and materials shall conform to the following as applicable at time of construction:

- of construction:

 Development Agreement (subdivision/phase)
 City of Saskatoon Standard Construction
 Specifications and Drawings: Parks Division in the
 edition that matches the date of the City approval of
 the Construction Drawings.

 All layout, including planting, paths, walls, formwork,
 rock work, furniture and equipment, shall be
 approved on site by the City prior to construction
 and installation. The City requires 24 hours
 notification prior to layout.

 Written dimensions take precedence over scaled
 dimensions. In case of discrepancy between listed
 quantities, symbols and labels on drawing(s), the
 symbols on drawing(s) shall be taken as correct.

 All dimensions are in metres unless otherwise
 noted.

- All conditions and dimensions shall be verified by the Contractor on site prior to commencement of work.
 All rocks/boulders are to be free of any spalling, cracks, crevices, or splinters. Selection shall be by the Designer/Contractor and approved by the City prior to placement.
 All furniture and equipment shall be installed per manufacturer's specifications and to current CSA standards. A letter of compliance to CSA guidelines shall be supplied prior to CCC.
 All trash receptacles shall be set back a minimum of 1.0m from the edge of all pathways.

	4	KD	2018/02/05	Location Revisions
	3	KD	2016/05/17	Information Revision
	2	KD	2016/02/17	Utilities Information
	1	KD	2016/01/28	Buidling Revision
١	REV	BY	DATE (Y/M/D)	REMARK

DESIGNED BY: DRAWN BY: KD

CHECKED BY: SBL SCALE (24 X 36" Sheet): SCALE (11 X 17" Sheet): 1:100 1:200 February 5, 2018

Building Layout Plan

Satellite Maintenance Yards

L-114